


Containment Cell	RoP Earth Fill (c.m.)	Containment Cell	EARTH FILL (c.m.)	PHASE (Dike)	BERM FILL (c.m.)
Cell 1	125 765±	Cell 1	189 456±	Phase 1	24 297±
Cell 2	35 032±	Cell 2	90 770±	Phase 2	23 340±
Cell 3a	211 520±	Cell 3a	263 807±	Phase 3	93 731±
Cell 3b	474 907±	Cell 3b	543 060±	Phase 4-1	33 336±
Cell 4a	287 041±	Cell 4a	347 319±	Phase 4-2	36 508±
Cell 4b	159 978±	Cell 4b	242 117±	Phase 4-3	22 834±
Cell 4c		Cell 4c	23 442±	Phase 4-2 and 4b	
Cell 5		Cell 5	200±	Phase 5	
Total	1 294 243±	Total	1 700 171±	Total	234 046±

PHASE (Access Road)	BERM FILL (c.m.)
Phase 1a	25 880±
Phase 2a	36 935±
Phase 2b	27 471±
Phase 3a	8 063±
Phase 4a	7 540±
Phase 4b	3 091±
Total	108 980±



Revised Jan. 24, 2018



SUBJECT TO CHANGE

Lakeview Waterfront Connection
Containment Cell & Access Berm - Fill Volume Calculation